

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address: Box # 6, Great Bend, Kansas 67530

Lease Name N. J. Weber "B" Well No. # 6

Location C S/2 SE NE Sec. 10 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3388

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Inc.

Address: Box 364, Great Bend, Kansas 67530 License No. # 399

Operation Completed: Hour 1 PM Day 29 Month 9 Year 1967

The Above well was plugged as follows:

8 5/8" 432' Cwc.

Sanded hole back to 3120' & dumped 5 sax cement with dump bailer. Pulled pipe.

Mud to 400', set 10' rock bridge, & displaced 5 sax cement. Let set over night.

Bailed hole dry, & displaced 25 sax cement. Mud to 40', set rock bridge, & dis-

placed 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/2/67

INV. NO. 6431-W