

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

14325

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address: Box 6 Great Bend, Kansas 67530

Lease Name N. J. Weber "B" Well No. 2

Location NW SW NE Sec. 10 Twp. 16 Rge. 12 (E) (W) X

County Barton Total Depth 3358

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 2P Day 30 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 3358' 10 3/4 csg set at 820'

5 1/2 csg perf. 3074-77

Filled 5 1/2 csg with sand to 3050' and dumped 5 sc cement with dump bailer.

Recov. 1435' of 5 1/2 csg.

Mud to 825' Set rock bridge (810-825) Set 35 sc cement plug (810-740)

Mud to 360' set rock bridge (350-360) Set 25 sc cement plug (300-350)

Mud to 30' set rock bridge (20-30) and dumped 10 sc cement to surface.(0-20)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Massey  
Well Plugging Supervisor

DATE 9/3/68

INV. NO. 8383-4