

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-009-19334-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Co.

Complete Address P.O. Box 287, Great Bend, Kas. 67530

Lease Name Christian Well No. D-2

Location NE-NE-SE Sec. 10 Twp. 16 Rge. 12 (East) (West)

County Barton Total Depth 3364'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelco Casing Pulling

Address Box 106 Chase, Kas. 67524 License No. _____

Operation Completed: Hour: 10:30 AM Day: 11 Month: 8 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 379' S.P. w/ common cement. 5 1/2" set at 3358' w/ 125 sacks common.
Top perf. 3102'. Plugged bottom w/ 75 sacks ⁵⁰ posmix - 42 gal. 3% Gel. Cl.
Shot pipe 6 times & recovered 1687'. Ordered 150 sacks ⁵⁰ posmix - 42 gal. 3% Gel. Cl.,
5 sacks bulls, 15 sacks Gel. + 8 5/8" plug. Pumped into 8 5/8" S.P., 4 sacks bulls, 12 sacks Gel.,
75 sacks cement, 12 sacks Gel., 1 sack bulls, released plug & followed w/ 75 sacks cement.

STATE CORPORATION COMMISSION

AUG 23 1982

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 350 pounds.

Amount of Surface Casing: 379' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Gerald R. White
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

Signed: _____
Conservation Division Agent

DATE 8-30-82

INV. NO. 9606