

15-009-06526-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. SW NE NE

LOCATION 7/2 - 7E/4

SEC. 11 TWP. 16 RGE. 12W

Cable tool

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Thill

Operator Advance Drilling Co. Address Box 44 Russell Kans.

Field _____ County Barton

Total Depth 3380 Feet.

Plugging Contractor Advance Drilling Co.

Plugging Contractor's License No. _____

Address Box 44, Russell Kans.

(Describe briefly the manner in which the well was plugged)

*Dry Cable tool, casing in hole @ 10" 765' 8 5/8"
@ 2150' 5 1/2" @ 3261 w/125 sq Cem. Cem not drilled
out in bottom. Perforated 2940'. Filled back
with sand to 2930' and dumped 5 sq Cem.
Knocked off and pulled 5 1/2" casing. Kept hole full
of mud while pulling 8" and 10" casing. Set
bridge at 275' and run 40 sq Cem. also rock
ledge at 20' and Cem to base of cellar w/15 sq Cem.*

PLUGGING
FILE SEC 11 T 16 R 12W
BOOK PAGE 32 LINE 27

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1954
CONSERVATION DIVISION
WICHITA, KANSAS

Warren H. Herner
District Conservation Agent

Date May 28, 1954