

15-009-20322-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Schauf "B" Well No. # 2

Location SE NW SW Sec. 11 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Garvey Drilling Company

Address: Route # 2, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6 AM Day 7 Month 12 Year 1968

The Above well was plugged as follows:

8 5/8" 286' Cwc.  
Circulated hole with heavy mud to 500', set plug with 1/4 sax hulls, & displaced  
40 sax cement thru drill pipe. Mud to 280', displaced 25 sax cement thru drill  
pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with Globe  
Cementing Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

Signed: Don Green  
Well Plugging Supervisor

DEC 10 1968

DATE 12/10/68 CONSERVATION DIVISION

INV. NO. 8980-W Wichita, Kansas