

44
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-185-12950-0000

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name Birdsall Well No. # 2

Location NE SE SE Sec. 21 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4051

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Kent Well Servicing Co.

Address: Box 470, Eldorado, Kansas License No. 394

Operation Completed: Hour 10:45AM Day 5th Month Oct. Year 1963

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cemented with 225 sacks. 3747' of 5 1/2" long
string. Plugged back to 3710'. Top perferation 3692'. Bottom of hole
was sanded to 3680', cemented with 5 sacks. Water was flowing from the
hole, a squeeze job was necessary. 15 sacks of Gel Mud and 75 sacks of
cement was pumped into the surface pipe, through an 8 5/8" swage, to a
pressure of 100 lbs. An 8 5/8" plug was pushed between the mud and the
cement. This cementing job was done by Globe Cementing Co.
2070' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/10/63
INV. NO. 9859-W