

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-185-00958-0000

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name Birdsall Well No. # 1

Location SE NE SE Sec. 21 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4071

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Kent Well Servicing Co.

Address: Box 470, Eldorado, Kansas License No. 394

Operation Completed: Hour 9:30AM Day 5th Month Oct. Year 1963

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cemented with 225 sacks. 3770' of 5 1/2" long
string. Plugged back to 3740'. Top perferation 3604'. Bottom hole plug
was pushed to 3590', rock bridge, cemented with 5 sacks. Water in the
hole was flowing, a squeeze job will be necessary, 15 sacks of Gel Mud
and 75 sacks cement was pumped into surface pipe, through an 8 5/8" swage,
to a pressure of 100 lbs. An 8 5/8" plug was run between the mud and the
cement. This cementing job was done by Globe Cementing Co.

2600' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 10/10/63

INV. NO. 1856-W

Signed: Archie Elving
Well Plugging Supervisor