

207

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15.185-60274-0001

Operator's Full Name Jard's Oil Operations

Complete Address 2740 E 45th Place Tulsa, OK 74105

Lease Name Ward Beaver Well No. 1

Location SW/NW/SE Sec. 21 Twp. 23 Rge. 14 (E) (W)W

County Stafford Total Depth 4042

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 5:00 PM Day 4 Month 6 Year 1971

The above well was plugged as follows:

206 ft 8 5/8 surface pipe cemented, circulated. 4042 ft 5 1/2 long
string cemented with 80 sacks. Top perf. 3992 ft. Sand back to
3900 ft, 5 sacks cement with bailer. Pulled 2720 ft 5 1/2. Pump 2
sacks hulls, 10 sacks gel., 100 sacks cement to surface.
Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: Russell B. Birstein
Well Plugging Supervisor

INVOICED

DATE 6-8-71
INV. NO. 3814-W