

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-185-19462-0000

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Piland "B" Well No. # 1

Location NW NE NE Sec. 23 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3755

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Co.

Address: Route 2, Great Bend, Kansas License No.

Operation Completed: Hour 7:30AM Day 27th Month Feb. Year 1964

The Above well was plugged as follows:

254' of 8 5/8" surface pipe, cemented with 275 sacks. Fluid level was
up in the hole, 1/2 sack hulls and 1st cementing plug was pushed to 240',
and cemented with 25 sacks, through the drill pipe. Hole was filled with
mud to 40', 2nd cementing plug, bridged with hulls, and cemented with
10 sacks to base cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/28/64

INV. NO. 8418-W