



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-185-00958-0000

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Troy Smith of Kent Well Servicing Co. has this
 date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name: Birdsall Well No. # 1

Location: SE NE SE Sec. 21 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4071 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

210' of 8 5/8" surface pipe, cemented with 225 sacks, 3770'
of 5 1/2" long string. Plugged back to 3740'. Top perforation
3604'. Push plug to 3590', rock bridge, cement with 5 sacks.
Fill hole with mud to 240', 10' rock bridge, cement with 25
sacks. Fill hole with mud to 40'. 10' rock bridge, cement
with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent