

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-185-19465-0000

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Jay Graves of Garvey Drilling Co. has this
date requested permission to plug the following described well:

Mr. Graves guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Birdsall Well No. # 3

Location: SW SE NW Sec. 29 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3815 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Graves was instructed to plug the well as follows:

255' of 8 5/8" surface pipe, cemented with 200 sacks.

Fill hole with mud to 250', 1st cementing plug, 1/2 sack hulls,

cement with 20 sacks. Fill hole with mud to 40', 2nd cement-

ing plug, 1/2 sack hulls, cement with 10 sacks to base cellar.

Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent