



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-195-20386-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Abercrombie of Rains & Williamson Drlg has this date requested permission to plug the following described well:

Mr. Abercrombie guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg. & Petroleum Resources

Complete Address: Box 18407 Wichita, Ks

Lease Name: Hohner A Well No. 1

Location: NE/SE/SW Sec. 31 Twp. 23 Rge. 14 (E) (W) W

County: Stafford Total Depth 4110 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Abercrombie was instructed to plug the well as follows:

260 ft 8 5/8 surface pipe cemented with 250 sacks. Pump
40 sacks cement to 600 ft. 2nd plug at 250 ft with 25 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Allied Cementing Co. Russell, Ks

Shobe, J

West Bend, Ks
Very truly yours,

L. Russell Binkston
Conservation Division Agent