



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-185-19462-0000

RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Lyle Hicks of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Piland "B" Well No. # 1

Location: NW NE NE Sec. 23 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3755 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hicks was instructed to plug the well as follows:

254' of 8 5/8" surface pipe, cemented with 275 sacks. Fill  
hole with drilling mud to 245'; 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls, and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving   
Conservation Division Agent