

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. C. R. Moore of National Coop. Refinery Assodas this
date requested permission to plug the following described well:

Mr. Ralph Booker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: Box # 6, Great Bend, Kansas 67530

Lease Name: N. J. Weber "B" Well No. # 6

Location: C S/2 SE NE Sec. 10 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3388 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" 432' Cwc.

Sanded hole back to 3120' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mud to 400', set 10' rock bridge, & displaced 5 sax

cement. Let set over night. Bailed hole dry, & displaced 25 sax

cement. Mud to 40', set rock bridge, & displaced 10 sax cement,

cementing to base of cellar.

Very truly yours,

Don L. Linn
Conservation Division Agent