

15-009-15717-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Morton Specter of Specter Pipe & Supply, Inc. has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas 67665

Lease Name: Christian Well No. # 1

Location: NW NE SW Sec. 10 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3316 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

10 3/4" 784' Cwc, Perf. 2840'.

Set bottom plug @ 2800' & dumped 5 sax cement with dump bailer. Pulled

pipe. Run tubing to 320'. Circulated hole with mud & displaced 50 sax

cement. Displaced 25 sax cement @ 200'. Pulled remaining pipe & dis-

placed 25 sax cement with pump truck, cementing to base of cellar.

Very truly yours,

Don Luman
Conservation Division Agent