

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,409-0000

LEASE NAME Cornwell

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-25

990 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 25 TWP. 23 RGE. 14 (X) or (W)

COUNTY Stafford

Date Well Completed 1-31-87

Plugging Commenced 1-31-87

Plugging Completed 1-31-87

LEASE OPERATOR Petro Locators, Inc.

ADDRESS P.O. Box 77 Pratt, KS 67124

PHONE#(316) 672-3040 OPERATORS LICENSE NO. 9740

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4105

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 840' w/50 sacks cement thru drill pipe

Next Plug: @ 435' w/50 " " " "

Top Plug: @ 40' w/ 10 sacks cement " " " "

15 sacks cement in Rat Hole fill up water well w/cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.


Leonard Williamson

(Employee of Operator) or ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1987

NOTARY PUBLIC

STATE OF KANSAS

My Appt. Exp. 5-5-90

My Commission Expires: 5-5-90

Dorothy M. Fry
Notary Public

FEB 4 1987

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 07-86

2-4-87

DRILLER'S WELL LOG

DATE COMMENCED: January 24, 1987
DATE COMPLETED: January 31, 1987

Petro Locators, Inc.
CORNWELL #1-25
C- N/2 SE SE
Sec. 25, T23S, R14W
Stafford County, Ks.

ELEVATION: 1934 K.B.

0' - 826' Surface Soil, Shale, Red Bed
826' - 847' Anhydrite
847' - 3012' Lime & Shale
3012' - 3405' Lime
3405' - 3442' Shale & Lime
3442' - 3545' Shale
3545' - 3566' Lime & Shale
3566' - 3819' Lime
3819' - 3921' Shale & Lime
3921' - 4007' Chert
4007' - 4063' Sand
4063' - 4105' Dolomite
4105' RTD

FORMATION DATA

Anhydrite	826'
Howard	3012'
Topeka	3095'
Hochner	3405'
Toronto	3425'
Douglas	3442'
Br. Lime	3545'
Kansas City	3566'
Esso K.C.	3819'
Viola	3921'
Stimpson	4007'
Arbuckle	4063'
RTD	4105'

Surface Pipe: Set new
8-5/8", 20# pipe @405'
w/215 sacks 60/40 pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 3rd day of February 1987.



Dorothy M. Hague
Notary Public

STATE CORPORATION COMMISSION

FEB 4 1987

CONSERVATION DIVISION,
Wichita, Kansas