


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 25 Twp. 23S Rge. 11W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NW
Lease Owner Natural Gas and Oil Company
Lease Name Radke Well No. 1
Office Address P. O. Box 105 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed February 27 19 53
Application for plugging filed May 23 19 60
Application for plugging approved May 24 19 60
Plugging commenced June 2 19 60
Plugging completed June 14 19 60
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 10 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Lans. K.C. Depth to top 3688 Bottom 3700 Total Depth of Well 4100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	201'	-0-
				7"	3754'	2629'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 6-2-60. Plugging completed 6-14-60.
Measured into plugged back total depth, 3740'. Plugged off bottom: Sanded back up hole to 3675' and dumped 5 sacks of cement. Worked and shot casing, not freed. Circulated and spotted 75 barrels of Oil. Pushed plug from 2750' to 3000'. Worked and shot casing. Shot 7" casing free at 2629'. Worked casing free. Pulled and laid down casing. Squeezed the well with 38 barrels of mud and 90 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a/ Forbes Casing Pulling Company 6-27-60
Address P. O. Box 221 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
K. W. FINNEY (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. W. Finney
P. O. Box 105 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 60

Richard R. Beach
Notary Public.

My commission expires July 27, 1963



15-185-00266-0000

DRILLER'S LOG

COMPANY Westgate-Greenland Oil Co., et al
 CONTRACTOR Westgate Drilling Corporation
 FARM Radke #1, NW NW NW 25-23S-14W
 Stafford County, Kansas
 COMMENCED February 8, 1953 - Rotary
 February 26, 1953 - Cardwell
 COMPLETED February 21, 1953 - Rotary
 February 27, 1953 - Cardwell

ELEVATION		
0	to	90
90	to	150
150	to	202
202	to	300
300	to	385
385	to	650
650	to	880
880	to	1780
1780	to	3579
3579	to	3842
3842	to	3857
3857	to	3900
3900	to	3947
3947	to	3991
3991	to	4054
4054	to	4100
4100	to	4100

Sand
 Sand and shale
 Shale
 Shale and shells
 Sand and shale
 Shale and red bed
 Anhydrite
 Shale and shells
 Lime and shale
 Lime
 Lime and shale
 Shale
 Lime and chert
 Chert
 Shale
 Arbuckle
 T. D. (R.B.)

RECEIVED
 STATE GEOLOGICAL COMMISSION
 MAY 24 1961
 DIVISION OF OIL AND GAS
 TOPEKA, KANSAS

Set 2011' of 1 1/2" 3/4" 32# surface pipe. Cemented with 200 sacks cement and 3 sacks calcium chloride.

Set 3754' of 7" casing. Cemented with 75 sacks cement.

TOPS: Anhydrite 850 Lansing 3568 Viola 3940
 Heebner 3416 Base K-C 3817 Arbuckle 4042
 Brown ls 3554 Cherty Cong 3919

DRILL STEM TESTS:

- 3589-3616, open 1 hour, rec. 420' gas, 240' gas cut mud, 710' BHP
- 3627-71, open 1 hour, fair to weak blow, rec. 421' mud, 117' 20#, BHP 1200, BHP 1310
- 3689-99, open 1 hour, rec. 2400' gas, 93' froggy bit, BHP 1200
- 3732-68, open 1 hour, rec. 35' watery mud, BHP 1130

Schlumberger run

Perforated 47 shot 3683-3700, saw raw gallon oil, 1000 CF
 Stabbed 75 BC in 4 hours.

Filed 25 BHPD Temporary Productivity Affidavit 2/27/53
 Material: 110 barrels - 2/26/53

CERTIFICATE

I, Don Allen, do hereby certify that the above and foregoing is a true and correct copy of log of the Radke #1, NW NW NW Section 25-23S-14W, Stafford County, Kansas, as reflected by files of the Westgate-Greenland Oil Company.

Don Allen
 District Manager
 Westgate-Greenland Oil Company
 1500 West 10th Street
 Topeka, Kansas 66604