

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 25 Twp. 23 Rge. 14 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE

Lease Owner John Lindas Oil, Inc.

Lease Name Batchman Well No. 1

Office Address 1316 Union National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 6, 1952

Application for plugging filed 8: am Comp. 9: PM Feb. 6 1952

Application for plugging approved Feb. 6 1952

Plugging commenced Feb. 6 1952

Plugging completed Feb. 6 1952

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 4075' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

205' 8 5/8" Casing Set plug @ 200' and 15 sacks cement. Set Plug @ 40' and 10 sacks cement.

2-13-52

FEB 13 1952

CONS. DIV. STATE CORP. COM.
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John Lindas Oil, Inc.

Address 1316 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Edward W. Wiens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edward W. Wiens

1316 U.N.B. Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 1952

Catherine Marcus
Notary Public.

My commission expires March 25, 1952

PLUGGING
FILE REC-257-23 R140
BOOK PAGE 143 LINE 26

DRILLING LOG

To: Lion Oil Company
Sunray Oil Corporation
Stanolind Oil & Gas Company
Feingold Oil Company
Dr. Hugh Hamilton
Mr. Edward G. Siebert
Garshaw Oil Company
John Lindas Oil, Inc.

15-185-00093-0000

Lease: Batchman #1

County: Stafford
Location: SW $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$
Section: 25-23S-14W
Elevation: ~~2166~~ DF

Rotary Total Depth: 4075'
Commenced: 1-22-52 Completed: 2-6-52
Casing: 205' of 8 5/8" casing with 150 sacks of cement and 2 sacks of calcium chloride.

Contractor: John Lindas Oil, Inc. Rig #3
1316 Union National Bank Bldg.
Wichita 2, Kansas

FIGURES INDICATE BOTTOM OF FOUNDATION

0	to	40	Surface Soil & Sand
40		121	Gravel & Sand
121		191	Shale
191		205	Shale Blue
205		305	Shale
305		370	Sand
370		600	Shale, Sand & Red Bed
600		885	Red Bed
885		890	Anhydrite
890		1410	Shale & Shells
1410		1590	Salt & Shale
1590		1790	Shale & Shells
1790		1960	Lime & Shale Streaks
1960		2028	Lime & Shale
2028		2070	Lime
2070		2220	Lime & Shale
2220		2295	Lime
2295		2545	Lime & Shale
2545		2690	Shale & Lime Streaks
2690		2895	Shale & Shells
2895		3020	Shale & Lime
3020		3111	Shale & Lime Streaks
3111		3145	Shale & Lime
3145		3225	Lime
3225		3310	Lime & Shale
3310		3365	Lime & Shale Streaks
3365		3485	Lime
3485		3555	Lime & Shale
3555		3905	Lime
3905		4005	Lime
4005		4045	Lime & Chert
4045		4075	Lime T.D.

PLUGGING
FILE SEC-25T-23S-14W
BOOK PAGE 143 OF 26

FEB 14 1952

STATE OF KANSAS)
)SS
COUNTY OF SEDGWICK)

15-185-60093-0000

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record and log of the well being drilled by John Lindas Oil, Inc. at the location above described.

Edward W. Wiens

Subscribed and sworn to before me, this sixth day of February, 1952.

My Commission expires the 25th day of March, 1952.

Catherine Quisenberry
Notary Public