

15-185-00204-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 26 Twp. 23S Rge. 14 (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE

Lease Owner Welch & Olsson Drilling Co. Inc.

Lease Name Coen Well No. 1

Office Address 1017 Union National Bank Bldg., Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 9-11 1953

Application for plugging filed 9-11 1953

Application for plugging approved 9-11 1953


Plugging commenced 9-11 1953

Plugging completed 9-11 1953

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4073' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 210' and set wooden plug. Cemented and displaced with cement truck 70 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.

Address 1017 Union National Bank Bldg., Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. E. Welch ~~(owner or operator)~~ or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address) _____

SUBSCRIBED AND SWORN TO before me this 16th day of September, 1953.

Marcella D. Davis
Notary Public.

My commission expires Feb. 27, 1956

RECEIVED
STATE CORPORATION COMMISSION
24-7366-8 53-53-20M
OCT 1953
CONSERVATION DIVISION
Wichita, Kansas
10-353

PLUGGING
FILE NO. 26-7-23-14a
BOOK PAGE 128

15-185-00704-0000

WELL LOG

WELCH & OLSSON DRILLING CO. INC.,
CONTRACTOR: Welch & Olsson Drilling Co. Inc.
Coen No. 1,
NW NW NE, Sec. 26-23S-14W,
Stafford County, Kansas.

Elevation: 1927' R. B.
Commenced Drlg: 8-29-53
Completed Drlg: 9-11-53
Production: D & A

Casing record:

Set 215' of 8 5/8" with 150 sacks cement.

(Figures indicate bottom of formations)

<u>FORMATIONS:</u>	<u>DEPTHS</u>	<u>FORMATION TOPS</u>
Sand	60'	Heebner 3408' - 1481'
Shale & Shells	215'	Brown Lime 3547' - 1620'
Red Bed	305'	Lansing 3562' - 1635'
Sand	360'	Base K. C. 3805' - 1878'
Red Bed	840'	Conglomerate 3900' - 1973'
Anhydrite	860'	Viola 3919' - 1992'
Shale & Shells	1065'	Simpson 3977' - 2050'
Shale	1725'	Arbuckle 4040' - 2113'
Lime & Shale	2605'	
Shale & Shells	2855'	
Shale & Lime	3093'	
Lime	3155'	
Lime & Shale	3250'	
Shale & Lime	3350'	
Lime	3408'	
Shale	3414'	
Lime	3458'	
Shale & Lime	3555'	
Lime	3845'	
Lime & Shale	3885'	
Lime	3912'	
Conglomerate	3917'	
Viola Lime	3978'	
Simpson Sand	3985'	
Sand	4036'	
Lime	4073'	

T. D.

STATE OF KANSAS,
COUNTY OF SEDGWICK, SS:

I hereby certify that the above is a true and correct copy of Drillers Log of Well drilled in the NW NW NE Sec. 26-23S-14W, Stafford County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.,

BY: R. E. Welch

R. E. Welch

Subscribed and sworn to before me this 16th day of September, 1953.

Marcella A. Jones
Notary Public

My Commission Expires: Feb. 27, 1956.

RECEIVED
STATE OF KANSAS
OCT 23 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
PAGE 28 LINE 27