

15-185-70386-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 31 Twp. 23S Rge. 14W (E) (W)  
Location as "NE/CNW&SW" or footage from lines NE SE SW  
Lease Owner Thunderbird Drilling, Inc.  
Lease Name HOHNER "A" Well No. 1  
Office Address 4328 E. Kellogg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-16-71 19  
Application for plugging filed 11-16-71 19  
Application for plugging approved 11-16-71 19  
Plugging commenced 11-16-71 19  
Plugging completed 11-16-71 19  
Reason for abandonment of well or producing formation commercial quantities of oil not found  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4110 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud up to 600' w/ 40 sx.  
Plug at 250' w/ 25 sx.  
Plug at 40' w/ 10 sx.  
Filled to bottom of cellar  
2 sx. for rathole

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.  
Address 435 Page Court, 220 West Douglas, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jerald W. Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerald W. Rains  
435 Page Court, 220 W. Douglas, Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of November, 1971

My commission expires  
TAMMY THOMPSON  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Comm. Expires Oct. 14, 1975

Tammy Thompson  
Notary Public.

COMPANY Thunderbird Drilling, Inc.

SEC. 31 T. 23S R. 14W  
LOC. NE SE SW


FARM Hohner "A" NO. 1

RIG. NO. 4  
TOTAL DEPTH 4110

COUNTY Stafford  
KANSAS

COMM. 11-4-71 COMP. 11-16-71

CONTRACTOR Rains & Williamson Oil Co., Inc.  
435 Page Court  
Wichita, Kansas 67202



CASINO  
20 10  
15 8 5/8" at 260' w/ 250 sx. cem.  
12 6  
13 5

ELEVATION  
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	218
Shale	265
Shale and Sand Streaks	540
Shale	904
Anhydrite	925
Shale	1821
Lime and Shale	2495
Shale and Lime	2800
Lime and Shale	3240
Shale and Lime	3670
Lime	4110
Rotary Total Depth	4110

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS  
County of SEDGWICK ss:

I, Jerald W. Rains of the Rains & Williamson Oil Co., Inc. Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Hohner "A" #1 well.

Jerald W. Rains  
Jerald W. Rains

Subscribed and sworn to before me this 18th day of November 19 71

My Commission Expires:

TAMMY THOMPSON  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Comm. Expires Oct. 14, 1975

Tammy Thompson  
NOTARY PUBLIC  
Tammy Thompson