

WELL PLUGGING RECORD

Stafford County. Sec. 33 Twp. 23 Rge. (E) 14 (W)

Location as "NE/CNW¼SW¼" or footage from lines NE NE NW

Lease Owner The Palmer Oil Corporation

Lease Name Gillmore Estate Well No. 1

Office Address 415 Union National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8/15/51 19

Application for plugging filed 8/15/51 19

Application for plugging approved 8/15/51 19

Plugging commenced 8/15/51 19

Plugging completed 8/15/51 19

Reason for abandonment of well or producing formation Dry Hole

Name of Conservation Agent who supervised plugging of this well.....C. D. Staugh.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4104 Feet
Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

4104 - 270' heavy mud

270 - Plug and 15 sacks cement.

40 - Plug and 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor..... The Palmer Oil Corporation

Address..... 415 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
A. H. Smith (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of September, 19 51.

My commission expires.....9/30/53.

6-51-20M

PLUGGING

FILE SEC-33T Y3 R 140

PAGE 104 LINE 8

15-185-00476-0000

WELL LOG - GILLMORE ESTATE #1

WELL OWNER: The Palmer Oil Corporation
CONTRACTOR: The Palmer Oil Corporation
Commenced: 8/1/51
Completed: 8/15/51
RESULTS: Dry Hole

Location: NE NE NW
Section 33-23S-14W
Stafford County, Kansas
Elevation: 1972 R.B.

Casing Record

8 5/8" - 282' cemented 175 sacks

Shale & shells	0	880
Anhydrite	880	900
Shale	900	1120
Shale & shells	1120	1856
Lime & shale	1856	2498
Shale & shells	2498	2603
Broken lime & shale	2603	2780
Shale & shells	2780	2932
Lime & shale	2932	3402
Lime	3402	3454
Lime & shale	3454	3497
Shale	3497	3576
Lime & shale	3576	3628
Lime	3628	3964
Conglomerate	3964	3998
Cherty lime	3998	4006
Chert & lime	4006	4060
Lime	4060	4065
Shale & sand	4065	4081
Arbuckle Lime	4081	4104 Rotary TD

Formation Tops (R.B.)

Heebner	3457
Brown Lime	3597
Lansing	3612
Base K.C.	3862
Cherty Conglomerate	3964
Simpson Sand	4036
Arbuckle	4081

DRILL STEM TEST - 4030 - 4060 Tool open 30 minutes.
Weak blow - recovered 15' very slight oil cut mud. BHP 15#.

This is to certify that the above is a true and correct log, according to the daily drilling reports.

SEP 20 1951 THE PALMER OIL CORPORATION
CONCESSION DIVISION
Wichita, Kansas

By A. H. Smith

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public in said county and state this 18th day of September, 1951.

Claf M. Holling
Notary Public

Commission expires: 9/30/53.

PLUGGING
FILE SEC 33-23-14W
BOOK PAGE 104 LINE 8