

15-185-01395-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 36 Twp. 23S Rge. (E) 14W (W)
Location as "NE/CNW/SW" or footage from lines SW NE SW
Lease Owner Range Oil Co.
Lease Name Vanhoozer Well No. #1
Office Address 402 Insurance Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May 19 19 69
Application for plugging filed May 20 19 69
Application for plugging approved May 23 19 69
Plugging commenced May 26 19 69
Plugging completed May 26 19 69
Reason for abandonment of well or producing formation Uneconomical to produce

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	222	none
				4-1/2"	3863	3108

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4 1/2" @ 3863' w/125 sks.
Sand 3865-3850'
3 sacks cement @ 3850'
Shot pipe @ 3202' & 3111'
Pulled 3108' 4 1/2" casing.
Rock bridge 215-205'
Sand 205'-200'
25 sks cement @ 200'
Mud to 40'
Rock 40'-30'
10 sks cement 30' to 4' below surface.

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1969
CONSERVATION DIVISION
Wichita, Kansas

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of June, 1969

My commission expires March 21, 1970

Notary Public.

15-185-61395-0000

ROTARY DRILLERS' LOG

OPERATOR: Range Oil Company, Inc.
301 Insurance Building
Wichita, Kansas

DRILLING COMMENCED: October 9, 1964

CONTRACTOR: Graves Drilling Co., Inc.
412 Union Center
Wichita, Kansas

DRILLING COMPLETED: October 17, 1964

CASING RECORD: 6 Jts. 238' of 8-5/8"
cemented with 250 sacks.

119 Jts. 3863' of 4 1/2"
cemented with 125 sacks.


LOCATION: Vanhoozer No. 1
SW NE SW
Section 36-23S-14W
Stafford County, Kansas

0 - 238	Sand & shale
238 - 849	Shale & shells
849 - 870	Lime & shale
870 - 958	Shale
958 - 1680	Shale & shells
1680 - 2120	Lime & shale
2120 - 2250	Lime
2250 - 2300	Lime with shale
2300 - 2707	Shale with lime
2707 - 3506	Lime & shale
3506 - 3578	Shale & lime
3578 - 3582	Brown lime
3582 - 3865	Shale & lime
3865	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Betty Brandt
Secretary



SS

Subscribed and sworn to before me, a Notary Public, this 22nd day of October, 1964.

My Notary Public Commission Expires:

March 26, 1966

Esther Sidener
Esther Sidener Notary Public

Handwritten signatures and notes at the bottom of the page.