

15-185-21359-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 36 Twp. 23 Rge. 14W  $\frac{1}{2}$  NW  
Location as "NE/CNW  $\frac{1}{4}$  SW  $\frac{1}{4}$ " or footage from lines  
C NW SW NE

Lease Owner Panther Energy Corp.  
Lease Name Cornwell Well No. 1  
Office Address 107 N. Market #410 Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plat

Dry Hole  
Date Well completed September 13, 1981  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced September 15, 1981  
Plugging completed 19  
Reason for abandonment of well or producing formation

Dry Hole  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
Producing formation Depth to top Bottom Total Depth of Well 4176  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		G.L.	428'	8 5/8		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from total depth to surface. Pumped a plug with 2 sks. of hulls and 140 sks. of 50/50 poz mix with 4% gel, 3% CC through plug container down casing. 10 sks. in rathole. Job completed @ 1:45 PM 9-15-81.

RECEIVED 9-21-81  
STATE CORPORATION COMMISSION  
21 1981  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing


STATE OF Kansas COUNTY OF Sedgwick  
Terry Michael (employee of owner) or (owner or operator)  
I, the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.


(Signature) Terry Michael  
107 N. Market #410 Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 1981

Denise A. Michael  
Denise A. Michael Notary Public.

My commission expires 5-27-85





15-185-21359-0000

# TEXAS ENERGIES, INC.

## DRILLERS' WELL LOG

Cornwell #1  
C NW SW NE, Sec. 36, TWP 23S, R14W  
Stafford County, Kansas

Commenced 08-30-81

Completed 09-13-81

OPERATOR: Panther Energy Corp.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 5 1981

CONSERVATION DIVISION  
Wichita, Kansas


<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	250	Sand	Spudded at 9:30 p.m. 8-30-81 Ran 416.15 of used 28# 8 5/8" set at 428' Cemented with 300 sacks common, 2.70 gel, 3.70 CC. Cement job by Allied. Cement did circulate. Plugged down @ 10:45 a.m. 8-31-81  Total depth of well 4176' Heavy mud from total depth to surface. Pumped a plug with 2 sks. of hulls and 140 sks. of 50/50 poz-mix with 4% gel, 3% CC through plug container down casing 10 sks. in rathole Job completed @ 1:45 p.m. 9-15-81
250	1100	Redbed	
1100	4176	Lime & Shale	

\*Well was plugged two days after well was completed.

STATE OF KANSAS )  
) ss.  
COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.


TEXAS ENERGIES EXPLORATION COMPANY, INC.

By:   
Lloyd E. Geoffroy, Jr., President

15-185-21359-0000

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the 29th  
day of September, 1981.

Darlene Butts  
Darlene Butts  
Notary Public



My Commission Expires:  
April 23, 1983