

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPHERSON County. Sec. 4 Twp. 21S Rge. (E) 1 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner ALADDIN PETROLEUM CORPORATION

Lease Name DOWNEY "B" Well No. 1

Office Address 809 PETROLEUM BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) GAS

Date well completed JANUARY 5 19 52

Application for plugging filed NOV. 1 19 56

Application for plugging approved NOV. 2 19 56

Plugging commenced NOV. 7 19 56

Plugging completed NOV. 16 19 56

Reason for abandonment of well or producing formation NOT PROFITABLE

If a producing well is abandoned, date of last production OCTOBER 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RUEL DURKEE

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2974 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	125'	NONE
				4-1/2"	3047'	1044'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2974 TO 2950 SAND BRIDGE

2950 TO 2915 4 SAX CEMENT

2915 TO 185 MUDDED

185 TO 175 ROCK BRIDGE

175 TO 120 20 SAX CEMENT

120 TO 15 MUDDED

15 TO CELLAR 5 SAX CEMENT

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1956

CONSERVATION DIVISION
Wichita, Kansas

11-28-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. & S. PIPE PULLING CO.

Address BOX 192 ELLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

J. M. JOHNSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. M. Johnson*

809 PETROLEUM BLDG. WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 27TH day of NOVEMBER, 19 56

Ray English
Notary Public.

My commission expires NOVEMBER 1, 1957

PLUGGING
FILE SEC 4 T. 21 R/W
BOOK PAGE 112 LI E 30

COMPANY: ALADDIN PETROLEUM CORPORATION FARM: DOWNEY "B" #1
 CONTRACTOR: LINDSLEY DRILLING CO. LOCATION: SW SW SE
 SEC: 4-21-1W
 COMMENCED: DECEMBER 6, 1951 McPHERSON COUNTY, KANSAS
 COMPLETED: DECEMBER 22, 1951 ROTARY CASING RECORD:
 JANUARY 5, 1952 CABLE TOOLS SET 8 5/8 W/100 SACKS
 CEMENT.
 ELEVATION: 1489 R.B. 4 1/2" RUN AT 3047 W/150
 PRODUCTION: 890 M.C.F./DA SACKS CEMENT.

FORMATION	FROM	TO
SAND, ROCK, SHALE	0	50'
SHALE, SHELLS	50'	125'
SHALE & LIME	120'	585'
ANHYDRITE	385'	410'
LIME	410'	670'
SHALE & LIME	670'	850'
SHALE & SHELLS	855'	1160'
LIME & SHALE	1160'	1530'
LIME & SHALE	1530'	1820'
LIME, SANDY SHALE	1820'	1965'
LIME	1965'	2010'
LIME & SHALE	2010'	2225'
SHALE & LIME	2225'	2358'
SHALE & LIME	2358'	2375'
LIME	2375'	2545'
LIME & SHALE	2545'	2685'
LIME & SHALE	2685'	2944'
LIME	2944'	2966'
MISSISSIPPI LIME & CHAT	2966'	2998'
MISSISSIPPI LIME	2998'	3062'
MISSISSIPPI LIME & CHAT	3062'	3117'
MISSISSIPPI LIME & SHALE	3117'	3227'
MISSISSIPPI LIME & SHALE	3227'	3264'
SHALE & LIME	3264'	3405'
SHALE & LIME	3405'	3422' T.D.
PB		2974 T.D. GR
PERF: 2961 TO 67' 36 HOLES ACIDIZED 1,000 GALS.		
TOPS: DOUGLAS SANDSTONE	2112	(-623)
LANSING	2336	(-847)
	2500-2515	
MISSISSIPPI LIMESTONE	2926	(-1437)

I HEREBY CERTIFY THIS TO BE A TRUE AND ACCURATE LOG OF THE ABOVE DESCRIBED WELL, AS SHOWN BY THE DAILY DRILLING RECORDS.

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1956

CONSERVATION DIVISION
Wichita, Kansas

ALADDIN PETROLEUM CORPORATION

By [Signature]

SUBSCRIBED AND SWORN TO BEFORE ME THIS 4th DAY OF March, 1952.

MY COMMISSION EXPIRES APRIL 23, 1952

[Signature]
NOTARY PUBLIC

PLUGGING
FILE SEC. 4 T. 21 R. 1W
BOOK PAGE 112 LINE 30