


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 35 Twp. 21 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE SE SW

Lease Owner A. Scott Ritchie
Lease Name Keller Well No. 1
Office Address 125 N. Market, Suite 950, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 22 19 76
Application for plugging filed June 22 19 76
Application for plugging approved June 22 19 76
Plugging commenced June 22 19 76
Plugging completed June 22 19 76
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug @ 450' w/40 sacks Common, 2% Gel,
Top plug @ 40' w/ $\frac{1}{2}$ sack hulls & 10 sacks Common, 2% Gel.

JUN 25 1976

GENERAL MANAGER
WICHITA, KANSAS

6-25-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.
Wayne Dobbs (employee of owner) or (~~owner or operator~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Wayne Dobbs
Box 823, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1976

My commission expires April 11, 1978

Dorothy M. Hogue
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: June 15, 1976
 DATE COMPLETED: June 22, 1976

A. Scott Richite
 "KELLER # 1"
 NE SE SW
 Sec 35-T21S-R15W
 Pawnee County, Kansas

ELEVATION: 1972 K.B.

0 - 180' Clay and Sand
 180 - 360' Shale, Clay, Sand Streaks
 360 - 500' Sand and Shale
 500 - 639' Red Bed
 639 - 930' Shale
 930 - 948' Anhydrite
 948 - 1150' Shale and Red Rock
 1150 - 2245' Shale and Shells
 2245 - 2989' Shale and Lime
 2989 - 3376' Lime
 3376 - 3380' Shale
 3380 - 3395' Shale and Lime
 3395 - 3495' Lime and Shale
 3495 - 3730' Lime
 3730 - 3831' Lime and Shale
 3831 - 3860' Chert
 3860 - 3916' Shale, Lime
 3916 - 3920' Dolomite
 3920' RTD

FORMATION DATA

Anhydrite	930
Topeka	2989
Heebner	3376
Toronto	3395
Brown Lime	3486
Lansing	3495
Base K.C.	3730
Viola	3831
Simpson, Shale	3860
Arbuckle	3916
RTD	3920

SURFACE PIPE:

Set used 8 5/8" pipe @ 639'
 w/175 sacks 60/40 Pozmix, 2% Gel,
 3% cc & 200 sacks Common, 2% Gel,
 3% cc.

A F F I D A V I T

STATE OF KANSAS }
 COUNTY OF BARTON } ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 23rd day of June, 1976.

Deborah M. Hague
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED
 STATE OF KANSAS
 JUN 26 1976
 COMMISSIONER OF REVENUE
 Topeka, Kansas