

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County. Sec. 15 Twp. 21S Rge. (X) 1 (W)

Location as "NE/CNW/SW" or footage from lines. SW NW SW  
Lease Owner. Kern Drilling Co., Inc.  
Lease Name. Boesker Well No. 1  
Office Address. Box 699, Magnolia, Arkansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 14, 1968  
Application for plugging filed March 14, 1968  
Application for plugging approved March 14, 1968  
Plugging commenced March 14, 1968  
Plugging completed March 14, 1968  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott, McPherson, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3440 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

505 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 1968

Betty Brandt

Notary Public.

My commission expires May 9, 1971

## ROTARY DRILLERS' LOG

OPERATOR: Kern Drilling Co., Inc.  
Box 699  
Magnolia, Arkansas

DRILLING COMMENCED: March 8, 1968

CONTRACTOR: Graves Drilling Co., Inc.  
505 Union Center  
Wichita, Kansas

DRILLING COMPLETED: March 14, 1968

CASING RECORD: 8 Jts. 205' 8-5/8"  
cemented with 200 sacks

LOCATION: Boesker No. 1  
SW NW SW  
Section 15-21S-1W  
McPherson County, Kansas

0 - 207	Sod, sand & clay
207 - 233	Shale & shells
233 - 648	Lime
648 - 1190	Shale & lime
1190 - 1575	Shale & shells
1575 - 2110	Shale & lime
2110 - 2346	Shale & sandy lime
2346 - 2470	Lime
2470 - 2620	Shale & lime
2620 - 2790	Lime
2790 - 2930	Shale & lime
2930 - 2978	Shale & cherty lime
2978 - 3285	Lime
3285 - 3388	Shale
3388 - 3440	Lime
3440	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves  
President

STATE OF KANSAS )  
SEBASTIAN COUNTY )

SS:

Subscribed and sworn to before me, a Notary Public this 20th of March, 1968.

Betty Brandt Notary Public

My subscription expires:  
May 9, 1971