


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

9

NORTH



Locate well correctly on above  
Section Flat

Mc Pherson County, Sec. 15 Twp. 21 Rge. 1 W(E) (W)  
Location as "NE/CNW/SW" or footage from lines Nw/ NW/NE  
Lease Owner Charles Johnson  
Lease Name Unruh Well No. 1  
Office Address 301 Peoples Bank Bldg. Mc Pherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 3-19 19 59  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced October 18 19 61  
Plugging completed Oct. 20 19 61  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones  
Producing formation Depth to top Bottom Total Depth of Well 3480 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					5 1/2"	3006'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3480' to 3390'. Dumped 5 sx of cement. Mudded hole to 200' ft. Set 10' of rock bridge. Dumped 20 sx of cement. Finished mudding hole to 34'. Set 10' of rock bridge. Dumped 8 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 25 1961

CONSERVATION DIVISION  
Wichita, Kansas

10-25-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas COUNTY OF Reno ss.  
Mrs. Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mrs. Art Lamb  
P.O. Box 983 Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of October, 19 61

My commission expires 1/16/65  
Gerald R. McMurray Notary Public.





15.113.00069.0000

RECEIVED  
STATE CORPORATION COMMISSION

OCT 17 1961

CONSERVATION DIVISION  
Wichita, Kansas

COMPANY: Norbrook Inc.  
 CONTRACTOR: Mallard Drilling Company  
 FARM: Unruh #1  
 LOCATION: NW NW NE Sec. 15-21-1W  
 Mc Pherson County, Kansas  
 COMMENCED: March 9, 1959  
 COMPLETED: March 19, 1959

0	to	30	Shale
30	to	70	Shale and shells
70	to	205	Shale and shells
205	to	400	Shale
400	to	590	Shale and shells
590	to	800	Lime
800	to	1455	Lime and shale
1455	to	1975	Lime and shale
1975	to	2115	Lime
2115	to	2343	Shale and lime
2343	to	2540	Lime
2540	to	2620	Lime
2620	to	2855	Lime and shale
2855	to	2961	Shale and lime
2961	to	3147	Mississippi
3147	to	3181	Chert and lime
3181	to	3255	Mississippi lime
3255	to	3403	Lime and shale
3403	to	3410	Lime-Hunter
3410	to	3490	Lime
3490	to	3505	Lime
		3505	T.D.

Set 205 feet of 8 5/8" surface pipe. Cemented with 140 sacks cement.

TOPS: Chat -- 2961 Hunter -- 3403 Viola -- 3484

Measurements taken from R.D.B. R.D.B. 58' from ground level.

DRY, ABANDONED AND PLUGGED.

#### CERTIFICATE

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Unruh #1, as reflected by filed of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 23rd day of March 1959.

Eva A. Sage

My commission expires March 12, 1962