


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

McPherson County. Sec. 11 Twp. 21S Rge. 1 (E) (W)

Location as "NE/CNW/SW" or footage from lines 3628' from south line: 1722' from East line of NE/4
Lease Owner Anderson-Prichard Oil Corp.
Lease Name Oliver Well No. 1
Office Address Box 142, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed Jan. 5 19 59
Application for plugging filed June 17 19 59
Application for plugging approved June 22 19 59
Plugging commenced June 29/29 19 59
Plugging completed July 2 19 59
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production No production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman 3484
Producing formation Depth to top Bottom Total Depth of Well 3484 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	218	None
				5 1/2	3484'	2520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured in to MD 3449'
Plugged off bottom and sanded to 3400'
Dumped 5 sacks cement
Worked and shot casing
Shot pipe off at 2520'
Laid down pipe
Mudded to 210'
Set rock bridge to 200'
Dumped 20 sacks cement
Filled hole with mud to 40'
Set rock bridge and mixed 10 sacks cement for cap on well

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Gerald M. Dougherty (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ANDERSON-PRICHARD OIL CORP.
(Signature) By: Gerald M. Dougherty
Box 142, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of July, 19 59

Verdella M. Hankins
Notary Public.

My commission expires Dec. 4, 1962

PLUGGING
FILE SEC 11 T. 21 R. 1W
BOOK PAGE 46 LINE 29

DRILLERS' LOG

Well Owner: Anderson-Prichard Oil Corporation
Farm Name: Oliver Well No. 1
Commenced: 11/25/58
Completed: 12/5/58
Total Depth: 3500'
Casing: 8 5/8" @ 218' cemented
5 1/2" @ 348 1/4' cemented

2' S & 72' W of
G. NE SW NE
Sec. 11-21S-1W

McPherson County, Kansas

Elevation:

Contractor: Peel Brothers, Inc.

Production:

Figures below indicate bottoms of formations:

Sand & shale	0 -	218
Blue shale		285
Shale & shells		400
Lime & shale		2150
Sand & shale		2275
Lime & shale		2709
Shale		2755
Shale & lime		2975
Lime & chert		3107
Chert		3166
Lime & chert		3195
Lime		3283
Shale		3415
Lime		3430
Shale & lime		3500
Total Depth		3500

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY *Jacob D. Matlock*

SUBSCRIBED AND SWORN to before me this 8th day of December, 1958

My commission expires: April 27, 1960

Luck Brant
Notary Public

RECEIVED
STATE COMMISSION COMMISSION

JUN 18 1959

CONSERVATION COMMISSION
Wich.

PLUGGING
FILE SEC. 11 T. 21 R. 11
BOOK PAGE 46 LINE 29