

15-185-12950-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 21 Twp. 23S Rge. 14/1E1 (W)  
Location as "NE/CNW%SW%" or footage from lines NE SE SE  
Lease Owner Pickrell Drilling Company  
Lease Name Birdsall Well No. 2  
Office Address 705 4th Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 12-08-53 19\_\_  
Application for plugging filed 9-26-63 19\_\_  
Application for plugging approved 9-28-63 19\_\_  
Plugging commenced 10-3-63 19\_\_  
Plugging completed 10-05-63 19\_\_  
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4051 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	215	circulated
				5 1/2	2747	2089.27

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Well had been plugged back to 2710 feet.  
Filled hole with chat from 2704 feet to 2680 feet  
and dumped 5 sacks cement.  
Pumped 15 sacks of mud, put in plug and pump  
75 sacks cement at 100 P.S. I.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kent Well Servicing Co.  
Address Box 470, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss. \_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mary Payne  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 9th day of October, 19 63

My commission expires June 8 1967 Eckelton E. P. Nelson  
Notary Public.

WILL 107

15-185-12950-0000

Company: GREENLAND DRILLING COMPANY

Sec. 21 T 23S R 11W

Farms: BIRDSALL

No. 2

Loc.: NE SE SE

Stafford Co., Kansas

Total Depth: 4051

Commenced: 11-25-53

Completed: 12-8-53

Contractor: Greenland Drilling Company

Casing: 8-5/8" 215'

5-1/2" 3747'

Elevation: 1944 R.B.

Prod.:

Figures Indicate Bottom of Formations

80	Sand and soil
155	Clay & sand
215	Shale & shells
315	Shale & shells w/red bed
370	Sand
847	Red bed w/shale & sand
872	Anhydrite
1125	Shale & shells
1675	Shale & shells w/salt streaks
1755	Shale & lime
1925	Lime & shale
2030	Lime w/shale breaks
2175	Lime & shale
2895	Shale & lime
2995	Lime & shale
3020	Shale
3080	Lime
3135	Lime & shale
3255	Sandy lime & shale
3330	Lime w/shale breaks
3415	Lime & shale
3419	Lime
3424	Shale
3466	Lime & shale
3515	Shale & lime
3556	Shale & sandy shale
3561	Lime
3567	Shale
3809	Lime
3863	Lime & shale
3877	Lime
3893	Chert & lime
3928	Shale, Lime & chert
3997	Lime w/chert
4037	Shale & sand
4046	Shale
4051	T.D.

TOPS:

Anhydrite	847
Kansas City	3565
Conglomerate	3877
Viola	3925
Simpson	3988
Arbuckle	4046
TDR	4051

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1955

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Richard S. Davis, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the #2 Birdsall well.

*Richard S. Davis*  
Richard S. Davis, Vice-President

Subscribed and sworn to before me this 22nd day of November, 1955.

My commission expires March 15, 1956.

*Verdina B. Rutledge*  
Verdina B. Rutledge, Notary Public