


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 5 Twp. 21 Rge. 10 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Leo J. Dreiling Oil Company
Lease Name Mulhouser Well No. 1
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 2-17-61 19
Application for plugging filed 2-17-61 19
Application for plugging approved 2-17-61 19
Plugging commenced 2-17-61 19
Plugging completed 2-17-61 19
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Toman
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3430' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	212'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rotary mud was used in filling up hole to a depth of 200' where a plug was set using $\frac{1}{2}$ sack hulls and 20 sacks cement and then filling hole to a depth of 35' where another plug was set using $\frac{1}{2}$ sack of hulls and 10 sacks cement and filling hole to top.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DREILING AND SONS, INC.
Address VICTORIA, KANSAS

STATE OF KANSAS, COUNTY OF ELLIS, ss.

L. Leo F. Dreiling a partner (employee or owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leo F. Dreiling

(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 1962

Roman Zimmerman

My commission expires August 14, 1965

Notary Public.

VICTORIA, KANSAS

WELL LOG

Company LEO J. DREILING OIL COMPANY

Farm VICTORIA, KANSAS No.

MULHOUSER 1

Total Depth 3430'

Comm. 2-8-61

Comp. 2-17-61

Contractor L. J. DREILING & SONS, INC.

VICTORIA, KANSAS

Cement Record

8 5/8 - - 212'

175 SAGS CEMENT

Sec. 5 Twp. 21 Rng. 10

Location NE SW SW

County RICE COUNTY, KANSAS

Elevation: D. F. 1742

G. R. 1740

Production:

D & A

Figures Indicate Bottom of Formations

0 - 110	SAND
110 - 212	RED ROCK
212 - 447	RED ROCK
447 - 472	ANHYDRITE
472 - 590	RED ROCK
590 - 1158	SHALE & BROKEN LIME
1158 - 1400	SHALE & LIME
1400 - 1590	SHALE & LIME
1590 - 1650	SHALE & LIME
1650 - 1750	SALT
1750 - 1770	SHALE & LIME
1770 - 1950	LIME & SHALE
1950 - 2060	SHALE & LIME
2060 - 2320	SHALE
2320 - 2490	SHALE & LIME
2490 - 2590	LIME & SHALE
2590 - 2703	LIME
2703 - 2850	SHALE & LIME
2850 - 2920	LIME
2920 - 2997	SHALE
2997 - 3080	LIME
3080 - 3121	LIME
3121 - 3180	LIME
3180 - 3240	LIME
3240 - 3313	LIME
3313 - 3350	LIME & CHERT
3350 - 3360	LIME
3360 - 3407	LIME
3407 - 3430	LIME
3430	TD

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo J. Dreiling, of the L. J. Dreiling & Sons, Inc.,
upon oath states that the above and foregoing is a true and
correct copy of the log from the Daily Drilling Report on your
Mulhouser # 1.

Leo J. Dreiling
LEO J. DREILING

Subscribed and sworn to before me this 22th day of May, 1961.

Ramon Zimmerman
NOTARY PUBLIC

My Commission Expires: August 14, 1965