


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County, Sec. 2 Twp. 21S Rge. 10W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW SW

Lease Owner Dakota Resources, Inc.
Lease Name O'NEILL Well No. 26-2
Office Address 2900 Sec. Life Bld, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 1/27 1981
Application for plugging filed 1/27 1981
Application for plugging approved 1/27 1981
Plugging commenced 1/27 1981
Plugging completed 1/27 1981

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production
----- 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation ----- Depth to top -- Bottom -- Total Depth of Well 3430
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	273'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

50 sks @ 300'
10 sks @ 40'
5 sks in rat hole
50/50 pos. 4% gel, 3% c.c.
By Howco

Handwritten: Fed
2-10-81

Handwritten: FF7

Stamp: CONSERVATION DIV.
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Co., P.O. Box 1389, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.
Roy Goans (employee of owner) or (~~owner~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Handwritten Signature: Roy Goans

P.O. Box 1389, Great Bend, KS 67530

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1981



Handwritten Signature: Ruth Brack

Notary Public.

My commission expires _____

DRILLER'S WELL LOG

DATE COMMENCED: 1/22/81
 DATE COMPLETED: 1/27/81

Dakota Resources, Inc.
 O'NEILL 26-2
 Sec. 2-21S-10W
 Rice County, Kansas

ELEVATIONS K.B.
 G.L.

FORMATION DATA

2846 - 2851' Shale
 2851 - 2980' Lime & shale
 2980 - 3006' Lime & shale
 3006 - 3336' Lime
 3336 - 3380' Sand
 3380 - 3430' Dolomite
 3430' RTD

Anhydrite
 Heebner 2846'
 Brown Lime 2980'
 Lansing 3006'
 Simpson Sand 3336'
 Arbuckle 3380'
 RTD 3430'

Wayne Lebsack, geologist

SURFACE PIPE:

Ran 6 jts. of 8-5/8" 24#
 used csg. Tally 266'.
 Set @ 273' w/280 sks. 60/40
 pos., 2% gel, 3% c.c.
 Cem. did circ. By Howco

PLUGGING:

50 sks @ 300'
 10 sks @ 40'
 5 sks in rat hole;
 50/50 posmix, 4% gel, 3% c.c.
 By Halliburton

AFFIDAVIT


STATE OF KANSAS)
 COUNTY OF BARTON) ss.

Roy Goans, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Roy Goans

Subscribed and sworn to before me this 6th day of February 1981.

Ruth Brack
 (Notary Public)



My commission Expires: