

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rice

County, Sec. 12 Twp. 21 Rge. 10 (E) 10 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW SW

Lease Owner Graham-Messman-Rinehart Oil Company

Lease Name Isern Well No. 1

Office Address 204 North Market, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed.....January 27.....19 52

Application for plugging filed.....January 30.....19 52

Application for plugging approved..... January 27..... 19 52

Plugging commenced	January 27	19 52
--------------------	------------	-------

Plugging completed.....January 28.....19 52

Reason for abandonment of well or producing formation.....Dry

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... 3429 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 180'; rock plug @ 180 w/15 sx. cement;

mud to 20', rock plug @ 20' w/ 5 sx. cement;

mud to surface.

1-31-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor.....Graham-Messman-Rinehart Oil Company

Address.....204 North Market, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) ~~or owner or operator~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. *[Signature]*

(Signature)

204 North Market, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 30th day of January, 19 52

My commission expires March 21, 1955

Notary Public.

23-8390-9 ~~SECRET~~ 6-51-20M

PLUGGING 
FILE SEC 12T 21 R 100
PAGE 19 LINE 3V

ISERN #1WELL RECORD

Location: NW NW SW
 Sec. 12-21-10W
 Rice County, Kansas

Commenced: January 19, 1952

Completed: January 27, 1952

Operator: G-M-R Oil Company

Elevation: 1700 R.B.

Contractor: G-M-R Oil Company

Production: D & A

Casing Record: 8 5/8" @ 182' w/150 sx.

LOG

Sand & Clay	180
Shale & Shells	1000
Shale & Shells	1260
Shale & Lime	1410
Anhydrite	1279
Shale & Lime	1585
Shale & Lime	1710
Shale & Lime	1851
Shale & Lime	2195
Shale & Lime	2465
Shale & Lime	2531
Lime & Shale	2610
Lime & Shale	2730
Lime & Shale	2794
Lime & Shale	2875
Lime & Shale	2995
Lime	3020
Lime	3070
Lime	3140
Lime	3194
Lime	3236
Lime	3295
Lime	3337
Shale & Lime	3357
Lime & Sand	3400
Lime	3429 T.D.

TOPS

Heebner	-	2821
Brown Lime	-	2954
Lansing	-	2974 (-1274)
Cherty Cong.	-	3318 (-1618)
Simpson Shale	-	3332 (-1632)
Simpson Sand	-	3359-69
Arbuckle	-	3399 (-1699)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

FILED
 STATE OF

GRAHAM-MESSMAN-RINEHART OIL COMPANY

JAN 31 1952

COMMISSIONER OF REVENUE
 TOCANTO, KANSAS

By

J. A. Gilliland

Subscribed and sworn to before me this
 30th day of January, 1952.

Oliver Carter
 Notary Public

My commission expires: March 21, 1955.

