


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 4 Twp. 23 Rge. 15 (E) W (W)



Location as "NE/CNWxSWx" or footage from lines NE NE NE
Lease Owner Stickle Drilling Company
Lease Name XXXXXXXXXXXX Grizzell Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-28-62 _____ 19____
Plugging completed 4-3-62 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4020 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	280'	None
				5-1/2"	4018'	3370'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, set plug @ 3540' and dumped 5 sacks of cement with dump bailer @ 3540'. Plug did not hold set another plug @ 3540' and dumped another 5 sacks of cement with dump bailer. Pulled 5 1/2" casing, pushed plug to 350' and set 10' rock bridge to 340'. Ran 20 sacks of cement. Set plug @ 240' and ran 11 sacks of cement. Bailed fluid to top of plug, ran 19 sacks of cement, mudded to 25', set 5' rock bridge to 20' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1962
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner of property~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of APRIL, 1962

My commission expires May 20, 1962 Milton J. Volin Notary Public.

15-145-01326-0000

Stickle Drilling Company, et al
Tulsa, Oklahoma

Tulsa, Oklahoma
January 21, 1957

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: January 4, 1957
Drilling Completed: January 18, 1957

Grizzell #1 - NE NE NE
Section 4-23S-15W, Pawnee
County, Kansas.
(Stickle #124)

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand & Shale	125
Shale	281
Shale & Shells	935
Anhydrite	960
Shale	1110
Shale & Lime	1830
Lime & Shale	1895
Lime	2310
Lime & Shale	2535
Shale & Lime	3180
Lime & Shale	3543
Lansing	3556
Lime	3885
Conglomerate	3895
Lime	3910
Lime & Chert	3930
Cherty Lime	3940
Sandy Shale & Lime	3965
Lime & Chert	4010
Arbuckle	4020 TD

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1962
CONSERVATION DIVISION
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Stickle Drilling Company, et al, Grizzell #1 - NE NE NE - Section 4-23S-15W, Pawnee County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires