

15-145-30178-0001


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 4 Twp. 23S Rge. 15 ~~XX~~ (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Max Cohen
Lease Name Grizzell Well No. 1
Office Address Box 13528, Phoenix, Arizona
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 8 19 54
Application for plugging filed September 4 19 63
Application for plugging approved _____ 19 _____
Plugging commenced September 7 19 63
Plugging completed September 11 19 63
Reason for abandonment of well or producing formation Uneconomic producer

If a producing well is abandoned, date of last production July 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Simpson Depth to top 3993 Bottom 4043 Total Depth of Well 4068 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Lansing-Kansas City</u>	<u>?</u>	<u>3562</u>	<u>3787</u>	<u>8 5/8</u>	<u>250</u>	<u>None</u>
<u>Simpson</u>	<u>Oil & wtr.</u>	<u>3993</u>	<u>4043</u>	<u>5 1/2</u>	<u>4067</u>	<u>3354'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement Plug @ 3600' 5 sks
Mud from 3559 to 260'
15' Rock Bridge 40 sks cement to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith
Address Box 156, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R Daniels
James R. Daniels
308 Schweiter Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 63

My commission expires November 18, 1966

Colleen Chapple
Colleen Chapple
Notary Public.

DRILLING LOG

15-145-30178-00-01

Operator: Max Cohen
Contractor: Armer Drilling
Commenced: 9/18/54
Completed: 10/8/54
Elevation: 2010 R.B.

Well: Grizzell No. 1
Location: NE NE SE Sec. 4-23S-15W
Pawnee County, Kansas
Casing: 8 5/8" at 250'
5 1/2" at 4067'

Figures indicate bottom of formation.

Sand	180'	Formation tops	
Shle & Shells	360'		
Shale	540'	Anhydrite	935'
Shale & Shells	935'	Heebner	3434'
Anhydrite	980'	Toronto	3454'
Shale & Sand	1360'	Br. Lime	3553'
Shale	1640'	Lans. K. C.	3562'
Shale & Shells	2110'	Base K.C.	3787'
Lime & Shale	3130'	Conglomerate	3892'
Lime	3434'	Viola	3915'
Shale (Heebner)	3438'	Simpson	3993'
Lime	3465'	Arbuckle	4043'
Shale & Sand	3553'		
Lime	3787'	Total Depth	4070'
Shale & Lime	3890'		
Conglomerate	3915'		
Lime	3993'		
Sand & Shale	4043'		
Lime	4070'		
Rotary Total Depth	4070'		

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1963

CONSERVATION DIVISION
Wichita, Kansas

The above log is based on information provided by the drilling contractor; on the report of the geologist employed to supervise drilling operations; and upon analysis of a radioactivity log ran on subject well. To the best knowledge of the undersigned this represents a true and correct log of the formations penetrated in the drilling of the Grizzell No. 1 well.

MAX COHEN

By: James R. Daniels
James R. Daniels
Geological Engineer

State of Kansas)
) SS
County of Sedgwick)

Subscribed and sworn to before me, a notary public, in and for said county and state on this 4th day of September, 1963.

My commission expires 11-18-66

Colleen Chapple
Colleen Chapple - Notary Public

15-145-30178-00-01

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

(Chester)

Company- MAX COHEN
Farm- Grizzell


No. 1

SEC. 4 T. 23 R. 15W
NE NE SE

Total Depth. 4070
Comm. 9-26-54 Comp. 10-9-54

County Pawnee
KANSAS

Shot or Treated.
Contractor. Armor, Inc.
Issued.



Elevation. 2019 KB

Production. 120 bbls. oil

Figures indicate Bottom of Formations.

sand	140
shale & sholls	400
sand	480
redbed	927
Anhydrite	948
shale & shells	1085
redbed, shale & sholls	1555
shale & lime	3485
shale	3570
shale & lime	3635
lime	3795
shale & lime	3945
chert	3959
cherty lime & shale	3980
lime	4020
shale	4045
lime	4070
Total depth	

Tops: K.B. Meas.	
Heebner	3434
Toronto	3454
Brown lime	3553
Lansing	3562
Base Kansas City	3787
Conglomerate	3892
Viola	3915
Simpson	3993
Artuckle	4043

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1964
CONSERVATION DIVISION
Wichita, Kansas