


WELL PLUGGING RECORD

15-145-3065-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County, Sec. 9 Twp. 23 Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW  
Lease Owner Stickle Drilling Company  
Lease Name Smith Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6-17-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed: 6-22-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4191 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FRDM | TD | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 289'   | None       |
|           |         |      |    | 5-1/2" | 4146'  | 3590'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to plug-back @ 4118', sanded hole to 4075' and dumped 4 sacks of cement @ 4075' with dump bailer. Pulled 87 jts. of 5 1/2" casing and circulated with 17 sacks of gel mud. Pulled 6 jts. of 5 1/2" casing and pumped in 30 sacks of cement. Pulled balance of 5 1/2" casing and capped well with 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1965

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

15-145-30165-0000

Stickle Drilling Company, et al  
Tulsa, Oklahoma

Tulsa, Oklahoma  
May 18, 1956

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: May 3, 1956  
Drilling Completed: May 15, 1956

Smith #1 - NE NE SW of  
Section 9-23S-15W,  
Pawnee County, Kansas

DRILLERS LOG

Depth Figures Indicate Base of Formation

|                       |         |
|-----------------------|---------|
| Sand                  | 140     |
| Shale & Clay          | 290     |
| Shale                 | 450     |
| Sand Dakota           | 530     |
| Shale, Shells, & Sand | 850     |
| Shale & Shells        | 980     |
| Anhydrite             | 1025    |
| Shale & Shells        | 1655    |
| Shale, Salt Lime      | 1930    |
| Lime Sandy            | 2075    |
| Shale & Lime          | 2395    |
| Lime & Shale          | 2510    |
| Shale & Lime          | 2985    |
| Shale & Shells        | 3150    |
| Lime & Shale          | 3290    |
| Lime Broken           | 3368    |
| Lime & Shale          | 3575    |
| Douglas               | 3629    |
| Brown Lime            | 3634    |
| Shale                 | 3637    |
| I. Kansas City        | 3675    |
| Lime                  | 3720    |
| Lime & Shale          | 3770    |
| Lime                  | 4002    |
| Viola                 | 4080    |
| Lime & Sand           | 4106    |
| Lime & Shale          | 4115    |
| Simpson               | 4123    |
| Shale & Lime          | 4165    |
| Lime                  | 4190 TD |

RECEIVED  
STATE CORPORATION COMMISSION

MAY 6 1965

CONSERVATION DIVISION  
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Stickle Drilling Company, et al - Smith #1 - NE NE SW of Section 9-23S-15W, Pawnee County, Kansas.

Frank E. Stickle  
Frank E. Stickle

William Bonham  
Notary Public

February 13, 1960  
My Commission Expires