

15-145-30080-000

STATE OF KANSAS

Form CP-4

STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

PAWNEE County, Sec. 9 Twp. 23S Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner KANSAS EXPLORATION Co.
Lease Name PETRO Well No.
Office Address 232 BONNIE BRAE, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 8-29- 19 65
Application for plugging filed 8-29- 19 65
Application for plugging approved 8-29- 19 65
Plugging commenced 8-29- 19 65
Plugging completed 8-29- 19 65
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation Depth to top Bottom Total Depth of Well 4160 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	297	8 5/8	297'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 425 FEET. SET FIRST PLUG AT 425 FEET WITH 1/2 SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 180 FEET. SET SECOND PLUG AT 180 FEET WITH 1/2 SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 35 FEET. SET THIRD PLUG AT 35 FEET WITH 10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BLDG., WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 8 day of SEPTEMBER 19 65

My commission expires Feb. 1, 1968
Barbara J. Layton Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS WELL LOG

RECEIVED
 STATE CORPORATION COMMISSION

SEP 15 1965

CONSERVATION DIVISION
 Wichita, Kansas

15-145-30080-0000

PETRO #1
 SE SW NE
 SECTION 9-23S-15W
 PAWNEE COUNTY, KANSAS

COMMENCED: AUGUST 20, 1965
 COMPLETED: AUGUST 29, 1965

OPERATOR - KANSAS EXPLORATION Co.

DEPTH		FORMATION	REMARKS
FROM	To		
0	140	SAND/GRAVEL	
140	295	SHALE	
295	970	RED BED	RAN 14 JOINTS OF 8-5/8" CASING, SET @ 297' w/285 SX. CEMENT.
970	1000	ANHYDRITE	
1000	1900	SHALE/SHELLS	
1900	2310	LIME/SHALE	
2310	2610	SHALE W/LIME STREAKS	
2610	3606	LIME/SHALE	
3606	3805	LIME	
3805	4000	LIME/SHALE	
4000	4050	LIME/CHERT	
4050	4101	CHERT/SAND/SHALE	
4101	4160	LIME	
4160	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS LOG FOR THE WELL DRILLED IN THE SE SW NE SECTION 9-23S-15W, PAWNEE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 31ST DAY OF AUGUST, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBURARY 1, 1968.