

15-445-01327-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County, Sec. 9 Twp. 23 Rge. 15 (E) W (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner Stickle Drilling Company  
Lease Name Smith Well No. 21  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6-14-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 6-16-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4159 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	None
				5-1/2"	4141'	2787'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3030', sanded hole to 3000' and dumped 4 sacks of cement @ 3000' with dump bailer. Pulled 72 joints of 5 1/2" casing and circulated pipe with 18 sacks of gel mud. Pulled 6 joints of 5 1/2" casing and pumped in 30 sacks of cement. Pulled balance of 5 1/2" casing, bailed hole to 30' and capped well with 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1965  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June, 1965

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

RECEIVED

JUN 22 1965

WICHITA, KANSAS

Stickle Drilling Company, et al  
Tulsa, Oklahoma

15-145-01327-0000 #116-1  
Tulsa, Oklahoma  
June 22, 1956

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: June 7, 1956  
Drilling Completed: June 20, 1956

Smith #A-1, NW NW SE of  
Section 9-23S-15W, Pawnee  
County, Kansas

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand	180
Sand, Shale & Shells	255
Shale & Shells	410
Sand, Shale & Red Bed	1060
Shale & Shells	1605
Sandy Lime	1855
Lime	2010
Lime & Shale	2110
Lime	2235
Lime & Shale	2470
Lime & Shale Streaks	2580
Shale & Lime	2990
Lime & Shale	3130
Shale & Lime	3165
Lime & Shale	3245
Lime	3385
Shale & Lime	3465
Lime & Shale	3570
Shale	3610
Brown Lime	3620
Lansing Lime	3645
Lime	3835
Lime & Shale	3883
Lime	3922
Lime & Shale	4022
Lime & Chert	4068
Shale & Lime	4079
Shale & Sand	4125
Shale & Lime	4146
Arbuckle	4161 TD

RECEIVED  
STATE CORPORATION COMMISSION

MAY 6 1965

CONSERVATION DIVISION  
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Stickle Drilling Company, et al, Smith A-1, NW NW SE of Section 9-23S-15W, Pawnee County, Kansas.

Frank E. Stickle  
Frank E. Stickle

Lillian T. Bonham  
Rotary Public

February 13, 1960  
By Commission Expires