

15-145-01017-0001


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 9 Twp. 23 Rge. 15 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines C S/2 NW/4 SE/4
Lease Owner Stickle Drilling Company
Lease Name Smith Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-21-65 _____ 19____
Plugging completed 6-22-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4179' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	409'	None
				5-1/2"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 50 sacks of gel mud and 90 sacks of cement to well, bridged hole @ 35', on top of cement, mudded hole to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1965

My commission expires May 20, 1968
Milton J. Volin Notary Public.

15-145-01017-00-01

Stickle Drilling Company, et al
Tulsa, Oklahoma

Tulsa, Oklahoma
September 9, 1957

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: August 24, 1957
Drilling Completed: September 5, 1957

J. T. Smith #3 - C S/2
NW SE - Sec. 9-23S-15W,
Pawnee County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand	90
Sand & Gravel	125
Clay	185
Shale	270
Sand & Gravel	310
Shale & Shells & Red Bed	411
Red Bed	440
Sand	500
Red Bed	685
Shale & Sand	1080
Shale & Shells	1175
Shale & Streaks Anhydrite	1250
Shale & Shells	1820
Shale & Lime	2020
Lime & Shale	2405
Shale & Lime	2950
Lime & Shale	3505
Lime	3544
Lime & Shale	3627
Lime	3878
Lime & Shale	3955
Lime & Chert	4067
Lime & Shale	4105
Lime, Shale, & Sand	4120
Shale, Lime, & Sand	4155
Shale & Lime	4160
Arbuckle	4179 TD

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1965
CONSERVATION DIVISION
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Stickle Drilling Company, et al, J. T. Smith #3, C S/2 NW/4 SE/4 of Section 9-23S-15W, Pawnee County, Kansas.

Frank E. Stickle
Frank E. Stickle

William T. Bonham
Notary Public

February 13, 1960
My Commission Expires