


15-145-01016-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 9 Twp. 23S Rge. 15 (W)
Location as "NE/CNWSW" or footage from lines SE SE NW
Lease Owner Stickle Drilling Company
Lease Name PETRO Well No. 1
Office Address 1027 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 26 November 19 56
Application for plugging filed 26 November 19 56
Application for plugging approved 26 November 19 56
Plugging commenced 26 November 19 56
Plugging completed 26 November 19 56
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage - Hoisington, Kansas
Producing formation none Depth to top Bottom Total Depth of Well 4185 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	approx. 150'	8 5/8"	291'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mixed mud in pits thoroughly with jets and placed heavy rotary mud from total depth to 280 feet through drill pipe.
A Halliburton plug and 1/3 sack of hulls were placed at 280 feet with 35 sacks of cement placed on top of this through the drill pipe.
Heavy rotary mud was placed to 35 feet.
A Halliburton plug and 1/3 sack of hulls were placed at 35 feet with 15 sacks of cement placed on top of this through the drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address 1027 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. B. Parriott (employment of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. B. Parriott
1027 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of November, 19 56

My commission expires Sept. 14, 1960

(Signature)
Notary Public.

PLUGGING
FILE SEC 9 T. 23 R. 15 W
BOOK PAGE 120 LI. E. 15

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1956
CONSERVATION DIVISION
Wichita, Kansas

11-29-56

15-145-01016-0000

Stickle Drilling Company, etal
Tulsa, Oklahoma

Tulsa, Oklahoma
November 27, 1956

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: November 14, 1956
Drilling Completed: November 26, 1956

Petro #1 SE SE NW Sec.
9-23S-15W, Pawnee
County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation:

Sand & Shale	190
Shale & Shells	260
Shale	293
Red Bed & Shale	965
Anhydrite	1000
Shale & Shells	1842
Shale & Lime	2025
Lime	2150
Lime & Shale	3285
Lime	3470
Lime & Shale	3545
Lime	3840
Lime & Shale	3880
Lime	3955
Lime & Shale	4015
Cherty Lime	4058
Lime	4065
Lime & Shale	4090
Simpson	4117
Shale	4170
Arbuckle	4185 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Stickle Drilling Company etal, Petro #1 SE SE NW, Section 9-23S-15W, Pawnee County, Kansas.

RECEIVED
CORPORATION COMMISSION

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE	SEC 9 T. 23 R. 15W
BOOK	PAGE 120 LINE 15