

4-060606

11-10
15.009.30190.00.01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1-21-65

SE NW SW /4 SEC. 04, 20 S, 11 W
1750 feet from S section line
1050 feet from E section line

Operator license# 6568Lease Grant well # 4Operator: Kaiser-Francis Oil CompanyCounty BartonAddress: P.O. Box 21468
Tulsa, OK 74121Well total depth 3333 feet ^{108,32}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 241 feetAband. oil well X, Gas well , Input well , SWD , D & A Plugging contractor: Mike's Testing & Salvage, Inc. License# -Address: P.O. Box 209 - Chase, Kansas 67524Company to plug at: Hour: 10:30A.M Day: 10 Month: November Year: 94Plugging proposal received from: Mike Kelso/RichardCompany: Mike's Testing & Salvage, Inc. Phone: 316-938-2943Were: Order 200 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1994

Plugging Proposal Received by: Herb DeinesPlugging operations attended by agent? All[], Part[], None[X]

COMMISSIONER D. WICHITA, KANSAS

Completed: Hour: 2:30P.M., Day: 10, Month: November, Year: 94

Actual plugging report: 8 5/8" to 241'. 4 1/2" to 3332' w/150 sxs.
LKC perfs only open. Set C.I.B.P. above top perf. at 3035' and spotted
1 sack cement on top of plug. Shot casing loose at 1928' and pulled to
1350'. Mixed and pumped 65 sxs. cement with 300# hulls. Pulled casing
to 575' and pumped 35 sxs. cement with 100# hulls. Pulled casing to
275' and circulated cement with 100 sxs. Pulled casing with cement
in cellar.

Remarks: Allied Cementing.Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO Plugged through TUBING , CASING X. Elevation: 1772 GLI did did not X observe the plugging.

INVOICED

D:TE

11-30-94

INV. NO.

41766

B# (agent)

Form CP-2/3