

12-23 4-031886

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-24,573-0000

SW SW NE /4 SEC. 15, 16 S, 12 W
2970 feet from S section line
2310 feet from E section line

Operator license# 31120 Lease Hoffman well # 1

Operator: Pelican Hill Oil & Gas, Inc. County Barton

Address: 2139 Ave. Espada Well total depth 3390 feet
San Clemente, California Conductor Pipe: 0 inch @ 0 feet
92672 Surface pipe 8 5/8 Inch @ 812 feet

110.18

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Allen Drilling Company License# 5418

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 23 Month: December Year: 93

Plugging proposal received from: Tim Lyon

Company: Allen Drilling Company Phone: _____

Were: Order 180 sxs. 60/40 pozmix - 6% gel.
Allied Cement Company.
Condition hole with at least 36 vis mud.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 7:30 P.M., Day: 23, Month: December, Year: 93

Actual plugging report: Spot cement plugs with drill pipe.
1st. plug @ 3300' w/25 sxs. d
2nd. plug @ 860' w/90 sxs.
3rd. plug @ 660' w/40 sxs.
4th. plug @ 40' w/10 sxs.
Corculate 15 sxs. in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1994

Remarks: Arbuckle 3300' - Anhy. 802' - 828'.
Condition of casing(in hole): GOOD ___ BAD ___ Anhy. plug: YES X NO ___
Bottom plug(in place): YES X, CALC ___, NO ___ Dakota plug: YES X, NO ___
Plugged through TUBING ___, CASING ___. Elevation: 1920 GL

CONSERVATION DIVISION
Wichita, Kansas

I did not observe the plugging. Carl Goodrow

INVOICED

DATE 1-21-94

INV. NO. 39752

12-23

MAR 15 1994

(agent)
Form CP-2/3