

7-24

2-070477 <sup>232</sup>  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

15.159-30270.0000

API NUMBER: 8-18-66

C SE NW, SECTION 8 TOWNSHIP 21 RANGE 9W

OPERATOR LICENSE # 5568 3300 FEET FROM S SECTION LINE  
3300 FEET FROM E SECTION LINE

OPERATOR Midway Drilling, Inc.  
NAME & P. O. Box 1325  
ADDRESS Great Bend, KS 67530-1325

LEASE NAME: Frederick #1  
COUNTY: Rice  
WELL TOTAL DEPTH: 3420' 111.15'

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 239'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing  
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 1:30 DAY: 24 MONTH: 7 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Monte  
COMPANY NAME: \_\_\_\_\_ PHONE: \_\_\_\_\_

WERE: sand to 3000' & 4 sx - 35 sx @ 1200' - 35 sx @ 700' -  
290' to surface.

PLUGGING PROPOSAL RECEIVED BY: Mike Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 4:30 DAY: 24 MONTH: 7 YEAR: 1992

ACTUAL PLUGGING REPORT:  
Sanded bottom to 3000' & 4 sx common - shot 4-1/2"  
csg off at 2100' - pulled to 1200' - loaded hole w/wtr  
& pumped 35 sx - pulled to 700' & pumped 35 sx - pulled  
to 300' & circ to surface.

REMARKS: Allied #3248 60/40 4%

RECEIVED  
INVOICED

DATE 8-10-92 8-7-92  
AUG 07 1992

Jack Luthi (AGENT)

INV. NO. 35916  
CONSERVATION DIVISION  
WICHITA, KS