

5 060087

9-17-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 159-22,201-0000

NE NW SE, SEC. 20, T 21 S, R 9 WXX

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7261

Lease Name Wellmann Well # 1

Operator: Pate-Dombaugh Petroleum

County Rice 115.38

Name & Address 804 Union Center

Well Total Depth 3550 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 377

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address Great Bend, KS 67530

Company to plug at: Hour: AM Day: 17 Month: 9 Year: 19 87

Plugging proposal received from Don Kern

(company name) Allen Drilling (phone) 793-5681

Remarks: Hole full of mud to 500'--50 sxs through drill pipe. Hole full of mud to 390'--35 sxs through drill pipe. Mud to 60', circulate 20 sxs to surface. Use bridge plug at 60'. 10 sxs in rathole.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30am Day: 17 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT Hole full of mud to 3528'--50 sxs cement through drill pipe.

Mud to 496'--50 sxs through drill pipe. Mud to 372'--35 sxs through

drill pipe. Bridge plug and 20 sxs @ 61'. 10 sxs in rathole.

Arbuckle top--3524' Used 60/40 poz, 6% gel

REATTACHED Cementing #2202

STATE CORPORATION COMMISSION

Remarks: SEP 22 1987

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION

Wichita, Kansas observe this plugging.

INVOICED

DATE 9-24-87

Signed Phil Worley (TECHNICIAN)

INV. NO. 18228 09-17 OCT 29 1987

15-159-20900-0000

February 6, 1984

Margarite Stang
Well Plugging Department
Conservation Division
State Corporation Commission
200 Colorado Derby Building
202 West First Street
Wichita, KS 67202-1286

file with CP-1


Re: Wellman A #1
SW SW SE SEC. 20-21-9W
Rice Co., Ks.
1435'
Thunderbird & Allied Cementing

Dear Ms. Stang;

A well plugging notice was issued by your department for the above referenced well on October 21, 1983. Since that time, ownership has been transferred from Thunderbird Drilling, Inc. to the landowner, R.G. Wellman. Mr. Wellman intends to develop the well for the natural gas to use for irrigating purposes. Therefore, the well will not be plugged at this time.

Thank you for your cooperation.

Sincerely,


R.G. Wellman

RECEIVED
STATE CORPORATION COMMISSION

FEB 08 1984

CONSERVATION DIVISION
Wichita, Kansas