

4-060515

3-23

15-009-15775-00-00

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1946

SE SE SE /4 SEC. 14, 16 S, 12 W  
330 feet from S section line  
330 feet from E section line

Operator license# 7323Lease Mary Weber East well # 9Operator: Paul HazenCounty Barton

Address: 200 W. 10th Street  
Ellinwood, Kansas 67526

Well total depth 3338 feet <sup>108.48</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 270 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    Plugging contractor: Co Tools License#    Address:    Company to plug at: Hour: 2:00P.M Day: 23 Month: March Year: 94Plugging proposal received from: Paul HazenCompany:     Phone: 316-564-2993

Were: Order 300 sxs. 60/40 posmix - 10% gel and hulls.  
Plug through tubing.  
Broke in with high fluid level.  
Salt section isolated top and bottom with cement.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 4:15P.M., Day: 23, Month: March, Year: 94

Actual plugging report: 8 5/8" to 270'. 5 1/2" to 3334'. Squeezed  
from 2389' - 2506' with 200 sxs. and at 1350' with 175 sxs. plus ran  
tubing to 1550'. Mixed and pumped 80 sxs. cement with cement to surface.  
Tubing parted on bad joint and left 20 joints of 2 3/8" in hole. Tied  
onto production casing and pumped 220 sxs. cement with 300# hulls.  
Cement in annulus in surface pipe with no annular returns. Max. 400#.  
S.I.P. 300#.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 30 1994

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD     BAD X Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING X, CASING    . Elevation: 1903 GL

I did[ X ] / did not[     ] observe the plugging.

DATE

4-6-94

INV. NO.

40220

3-23

JUN 02 1994

(agent)

Form CP-2/3