

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22388-00-00
Spot: SESWNW Sec/Twnshp/Rge: 7-21S-10W
2260 feet from N Section Line, 990 feet from W Section Line
Lease/Unit Name: FREDRICK A Well Number: 1-7
County: RICE Total Vertical Depth: 3450 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 224
Production: Size _____ feet:
Liner: Size _____ feet:

8/12.13

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/05/2001 9:10 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: DARROL Company: STERLING DRILLING CO. Phone: _____

Proposed Plugging Method: 35sxs at top of Arbuckle. 35sxs @1250'. 35sxs @900'. 35sxs@375'. 25sx@60'. 15sxs in Rathole. 10sxs in Mousehole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 06/05/2001 9:10 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The drill pipe was run open end to 3360', where 35sxs of cement was spotted. The drill pipe was pulled to 1250', where 35sxs of cement was spotted. The drill pipe was pulled to 900', where 35sxs of cement was spotted. The drill pipe was pulled to 375', where 35sxs of cement was spotted. The drill pipe was pulled to 60', where 25sxs of cement was circulated to surface. The Rat hole was circulated with 15sxs of cement. The Mouse hole was circulated w/10sxs of cement.

INVOICED
DATE 6-7-01
INVOICE NO. 2001061902

RECEIVED
KCC DISTRICT #2
JUN 05 2001
WICHITA, KS

Remarks: ACID SERVICE CO. #03585 60/40 POZ 4%GEL

Plugged through: DP

District: 02

Signed 
(TECHNICIAN)