

1 040432

6-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,888-6000
C SE SW, SEC. 9, T 23 S, R 15 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635
Operator: Great Bend Casing Pullers, Inc.
Name & Address P.O. Box 768
Great Bend, KS 67530

Lease Name Smith Well # 1
County Pawnee 136.05
Well Total Depth 4186 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 383

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 20 Month: 6 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3875' PBDT 3848' Perfs at 3773-76'
1st plug sand back to 2630' and dump 4 sx cement on top of sand bridge through bailer,
2nd plug pump down 8 5/8" surface with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 20 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 2630' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 150 psi.

RECEIVED
JUN 27 1990
6-29-90
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by BJ Services! Recovered 2016' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I, Steve Pfeifer observe this plugging.

DATE 7-3-90
INV. NO. 28536

Signed Steve Pfeifer
(TECHNICIAN)