

To: 1 051537 3-17  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
700 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,394-6000 910  
NE SE NW, SEC. 10, T. 23 S, R. 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30870  
Operator: Reynolds-Rexwinkle Oil, Inc.  
Name & Address 212 N. Market, Suite 402  
Wichita, KS 67202

3630 feet from S section line  
2970 feet from E section line  
Lease Name Smith Well # 1-10  
County Pawnee 134.87  
Well Total Depth 4150 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418  
Address P.O. Box 1389, Great Bend, KS 67530-1389

Company to plug at: Hour: 11 p.m. Day: 16 Month: 3 Year: 19 92

Plugging proposal received from Mike Kern  
(company name) Allen Drilling Company (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 950-968'  
1st plug at 960' with 50 sx cement,  
2nd plug at 330' with 40 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 1:30 a.m. Day: 17 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement,  
2nd plug at 380' with 40 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement. 3-19-92

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

I (we) (do) (do not) observe this plugging.

DATE 4-7-92  
INV. NO. 34890  
3-17

Signed Richard M. Lacey  
(TECHNICIAN)

FOR KCC USE:

EFFECTIVE DATE: 3-9-92

DISTRICT # 1

SGA7  Yes  No

State of Kansas

NOTICE OF INTENTION TO DRILL

145-21,394-0000

FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 9, 1992  
month day year

Spot NE - SE - NW Sec 10, Twp 23, S. Rg 15 X West East

OPERATOR: License # 30870  
Name: Reynolds-Rexwinkle Oil, Inc.  
Address: 212 N. Market #402  
City/State/Zip: Wichita, Kansas  
Contact Person: Daniel M. Reynolds  
Phone: 316-269-1233

3630 feet from South / ~~North~~ line of Section  
2970 feet from East / ~~West~~ line of Section  
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Pawnee  
Lease Name: Smith Well #: 1-10  
Field Name: Wildcat

CONTRACTOR: License #: 5418  
Name: Allen Drilling Company

Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): Arbuckle

Well Drilled For: Well Class: Type Equipment:  
X Oil Enh Rec Infield X Mud Rotary  
Gas Storage Pool Ext. Air Rotary  
OWWO Disposal X Wildcat Cable  
Seismic # of Holes Other  
Other

Nearest lease or unit boundary: 330  
Ground Surface Elevation: est 2002 feet MSL

If OWWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Water well within one-quarter mile: X yes no  
Public water supply well within one mile: no yes X no

Depth to bottom of fresh water: 80  
Depth to bottom of usable water: 300  
Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 250 320  
Length of Conductor pipe required: none

Projected Total Depth: 4150  
Formation at Total Depth: Arbuckle

Water Source for Drilling Operations:  
X well farm pond other

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth: \_\_\_\_\_

DVR Permit #: Will provide  
Will Cores Be Taken?: yes X no

Bottom Hole Location: \_\_\_\_\_  
Exp. 9/4/92

If yes, proposed zone: \_\_\_\_\_

AFFIDAVIT

320' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Micky Kern INIT. \_\_\_\_\_

SPUD DATE 3-9-92 320'

LENGTH SURFACE PLANNED 320'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 3/4" @ 350 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- 950 B- 948 ELEVATION \_\_\_\_\_

TD 4150 FORMATION \_\_\_\_\_

RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
SX \_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_

Arbuckle Plug @ 50 Ft. W/ 8 SX

Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Anhydrite Base @ 260 Ft. W/ 50 SX

1/2 Base Anyh. @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Bottom Surface @ 380 Ft. W/ 40 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX

WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
Hauling \_\_\_\_\_

TECHNICIAN R. L. DATE 3-13-92

TYPE OF CEMENT 60/40 per 6 page 1

STARTING TIME 11:00 (AM/PM) DATE 3-16

COMPLETION TIME 1:30 (AM/PM) DATE 3-17

CEMENT COMPANY Allen