

21020-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-~~24020~~
NENW SEC. 10, T23S, R15W

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5652

LEASE NAME Irma "B" WELL # 1

OPERATOR: Mustang Drilling + Exploration
NAME & ADDRESS: Box 1425
Great Bend Kansas 67530

COUNTY Pawnee
WELL TOTAL DEPTH 4140 \$134.55 FEET
CONDUCTOR PIPE: SIZE FEET
SURFACE CASING: SIZE 8 5/8 FEET 409

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D&A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Rockhold Engineering Inc LICENSE NUMBER 5111

ADDRESS Box 698 Great Bend Kansas 67530

COMPANY TO PLUG AT: HOUR: 3:30 pm DAY: 5 MONTH: July YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Terry THORN

(COMPANY NAME) Rockhold Engineering (PHONE)

WERE: Sand Bottom to 4030 + dump 4sx cement
Pump down 8 5/8" with 3sx hulls - 10gel -
70sx cement - 10gel - 1hull - 1 wiper plug -
150sx cement using 60/40 poz mix 2% gel
3% cc

PLUGGING PROPOSAL RECEIVED BY Richard W. Lacey
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:45 pm DAY: 5 MONTH: July YEAR: 1983

ACTUAL PLUGGING REPORT Plugged as Proposed in above paragraph

Maximum pump pressure 500 psi

Shot in pressure 250 psi

Recovered 1600' of 4 1/2" production casing

500 pumped the cement

REMARKS:

RECEIVED
STATE CORPORATION COMMISSION

JUL 07 1983

CONSERVATION DIVISION
Wichita, Kansas

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 7-19-83
INV. NO. 4875-W

FORM CP-2/3
REV. 6-83