

12-7

To: 1 070622
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,865-0660
C SE NE, SEC. 16, T 23 S, R 15 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5010
Operator: Knighton Oil Company, Inc.
Name & Address: 710 Petroleum Building
Wichita, KS 67202

Lease Name Petro Well # 1
County Pawnee 134.88
Well Total Depth 4150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 7 Month: 12 Year: 19 88

Plugging proposal received from Clay Duntz
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 2140' PBD 2140' Perfs at 2010-66' (4 sets)
1st plug pump 30 sx cement to 50' above perfs,
2nd plug pump 3 sx hulls, 5 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
DLC 9 1988

12-9-88

Plugging Proposal Received by Dan Goodrow & Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4:30 p.m. Day: 7 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx common cement,
2nd plug pumped 300 lbs. hulls, 5 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
and 100 sx cement.

Maximum pressure 700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-12-88
INV. NO. 23320

Signed Dan Goodrow
(TECHNICIAN)