

1031509

TO: STATE CORPORATION COMMISSION

11-06

API NUMBER 15-145-20,474-0000
SW NW SE SEC. 19, T 23 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WURM A WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY PAWNEE 132.80

OPERATOR LICENSE # 3959 WELL TOTAL DEPTH 4086 FEET

OPERATOR: SIROKY OIL MANAGEMENT PRODUCTION CSG: SIZE 5 1/2" @ 4086' WITH 100 SX

NAME AND PO BOX 464 SURFACE CASING: SIZE 8 5/8" @ 368' WITH 275 SX

ADDRESS PRATT, KS 67124

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 9:45 AM DAY: 06 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 4036'-4048'

1ST PLUG SAND TO 3980' AND 5 SX CEMENT. 2ND PLUG PUMP 3 HULLS, 10 SX GEL, 50SX CEMENT,

10 SX GEL, 1 HULL, 8 5/8" WIPER PLUG, 150 SX CEMENT. MAXIMUM PSI PRESSURE AT 600#.

SHUT IN AT 350#.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 06 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT 11-11-98

1ST PLUG SAND BACK TO 3980' AND 5 SX CEMENT. 2ND PLUG PUMP 3 HULLS, 10 SX GEL, 50 SX

CEMENT, 10 SX GEL, 1 HULL, 8 5/8" WIPER PLUG, 150 SX CEMENT. MAXIMUM PRESSURE AT 600#.

SHUT IN AT 350#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Steve Durrant (TECHNICIAN) FORM CP-2/3

11-23-98
60370